

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-30

2-070792

API Number: 15-095-21023 0000

SW SE NE SECTION 20 TWP 29 RANGE 08W

OPERATOR LICENSE #31191 2970 FEET FROM S SECTION LINE
OPERATOR R & B OIL AND GAS INC. 990 FEET FROM E SECTION LINE
NAME & ADDRESS P.O. BOX 195
ATTICA, KS 67009

LEASE NAME KROESCH #1
COUNTY KINGMAN
WELL TOTAL DEPTH 4202' 136.57
PIPE 4 1/2" @ 4202'
SURFACE CASING 8 5/8" @ 207'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: P.O. BOX 337, ATTICA, KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: 1:00 DAY: 30 MONTH: 9 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPP

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: (316) 254-7893

WERE: C.I.B.P. @ 2200' - 2 SACKS
35 SACKS @ 1300'
35 SACKS @ 800'
260' TO 0

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL X PART _____ NONE _____

COMPLETED: HOUR: 5:00 DAY: 30 MONTH: 9 YEAR: 1998

ACTUAL PLUGGING REPORT: C.I.B.P. AT 2200' WITH 2 SACKS OF COMMON. SHOT 4 1/2" CASING OFF AT 1500'.
PULLED TO 1300', PUMPED 35 SACKS. PULLED TO 800', PUMPED 35 SACKS. PULLED TO 260', CIRCULATED
CEMENT TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: ALLIED #9774, 60/40 POZ, 4% GEL.

10-07-98 OCT 07 1998

I DID OBSERVE THIS PLUGGING.

CONSERVATION DIVISION
WICHITA, KS

Jack Luthi
JACK LUTHI

INVOICED
DATE 10-8-98
INV. NO. 51427

FORM CP-2/3
REV. 3/90

9-30 JAN 29 1999