

4-6

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-20,409 0000
C SE NW, SECTION 23 TOWNSHIP 29 RANGE 8W

OPERATOR LICENSE # 4706 3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR MESSENGER PETRO INC
NAME & RR 1 BOX 172 A-1
ADDRESS KINGMAN KS 67068

LEASE NAME: IANthⁿ IANⁿ YOUNG #1 140.23
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4315' PB 4266'
PIPE: 5-1/2" @ 4315'

SURFACE CASING: 8-5/8" @ 273'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JON MESSENGER
COMPANY NAME: MESSENGER PETRO INC PHONE: _____

WERE: PERF 4206'-37' & 4244'-54' - SAND BACK TO 4150' &
CAP W/5 SX CMT - 35 SX @ 1200' - 35 SX @ 750' - CIRC
CMT 320' TO 0'

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

COMPLETED: HOUR: 17:00 DAY: 6 MONTH: 4 YEAR: 1994

ACTUAL PLUGGING REPORT:
PERFS WERE COVERED W/SAND FROM 4315' TO 4155' &
CAPPED W/5 SX CMT - 5-1/2" WAS RECOVERED FROM 2700' &
PULLED TO 1199' & 35 SX SPOTTED - PIPE PULLED TO 777' &
35 SX CMT SPOTTED - PULLED PIPE TO 344' & CIRC CMT

REMARKS: ALLIED CMT 60/40 4% GEL

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 4-25-94

INV. NO. 40332
4-6

/s/

Steve Van Gieson

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 1994
04-20-94

CONSERVATION DIVISION
WICHITA
FORM EP-2/93
REV. 3/90