

1 060011

12-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,337-0000

C SW SW, SEC. 22, T 24 S, R 22 W/EX

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Mages Well # 1

Operator: D.R. Lauck Oil Company, Inc. and

County Hodgeman 153.24

Name & Address Pickrell Drilling Company

Well Total Depth 4715 feet

221 South Broadway, Suite 400

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 15 Month: 12 Year: 1989

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company (phone) 316-262-8427

were: to fill hole with heavy mud and stop cement through drill pipe Anhydrite 1470-1507'

1st plug at 1500' with 50 sx cement, 2nd plug at 750' with 80 sx cement,

3rd plug at 440' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:15 p.m. Day: 15 Month: 12 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 750' with 80 sx cement,

3rd plug at 440' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

12-20-89

RECEIVED STATE CORPORATION COMMISSION

DEC 20 1989

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not) observe this plugging.

DATE 1-5-90

Signed Case Morris (TECHNICIAN)

WEL. NO. 26906