

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,109-0000 ✓

SE/4, Sec. 25, T 24 S, R 72 WK

380' feet from ~~W~~S section line

330' feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9149

Lease Name V.L. KATZ Well # 1

Operator: KENNETH E. KOGER  
Name & Address 2933 CROCKETT  
FT. WORTH, TX 76107

County HODGEMAN

Well Total Depth 4406 feet 143.20

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8 feet 455

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor COUGAR OIL COMPANY License Number 5138

Address 555 N. WOODLAWN, SUITE 114, WICHITA, KS 67208

Company to plug at: Hour: Noon Day: 6 Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO GARY BAGBY

(company name) COUGAR (phone) \_\_\_\_\_

were: to use 60/40 Pozmix, 2% gel - 3% CC AND SPOT THE  
1<sup>ST</sup> plug @ 1500' w/ 50 sy - 2<sup>ND</sup> plug @ 720' w/ 70 sy  
3<sup>RD</sup> plug @ 40' w/ solid bridge, plug and 10 sy.  
Circulate 15 sy in the rat hole and 10 sy  
in the mouse hole.

Signed R. Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3pm Day: 6 Month: JAN Year: 1984

ACTUAL PLUGGING REPORT plugged as ordered.  
Cementing by Allied.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not) observe this plugging.

INVOICED  
DATE 1-16-84  
INV. NO. 9104-W

Signed R. Barluttan (TECHNICIAN) ✓