

1
110083

10-11-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,289-0000
C NW SE, SEC. 27, T 24 S, R 22 W/R
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 North Market, Suite 1000
Wichita, KS 67202

Lease Name Rosproy Well # 1
County Hodgeman 157.63
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302
Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 11:15 p.m. Day: 10 Month: 10 Year: 19 87

Plugging proposal received from Steve Dunham
(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2387'
Anhydrite 1516'

1st plug at 1556' with 50 sx cement, 2nd plug at 800' with 50 sx cement,
3rd plug at base of surface pipe plus 30' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 11 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,
2nd plug at 900' with 50 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (Do not observe this plugging.)

DATE 10-20-87
INV. NO. 18585
10-11

Signed James R. Kapp
(TECHNICIAN)