

1 070345

MAY 2 1 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,277-0000  
C SE SE, SEC. 29, T 24 S, R 22 W/E  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6785  
Operator: Robert Schulein  
Name & Address 1776 Lincoln Street, Suite 811  
Denver, CO 80203

Lease Name Downey Well # 16-29  
County Hodgeman 156.00  
Well Total Depth 4800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302  
Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 7:40 a.m. Day: 21 Month: 5 Year: 19 87

Plugging proposal received from Ross Crawford

(company name) Red Tiger Drilling Company (phone) 316-263-1201  
Elevation 2380'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1495-1530'  
1st plug at base Anhydrite with 50 sx cement, 2nd plug at 750' with 80 sx cement,  
3rd plug at 440' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:50 a.m. Day: 21 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement,  
2nd plug at 750' with 80 sx cement,  
3rd plug at 440' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 5-27-87  
INV. NO. 17004

Signed Dan Goodrow  
(TECHNICIAN) RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1987  
CONSERVATION DIVISION  
Wichita, Kansas