

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-20,730
SW 1/4, Sec. 29, T 29 S, R 22 W 1/4
(SW-SW-SW) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

feet from W/E section line

Operator: BEREN CORPORATION
Name & Address: 970 FOURTH FINANCIAL CENTER
Wichita, KS 67202

Lease Name GERRITZEN Well # 1

County HODGEMAN

Well Total Depth 4780' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 565'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 8:30 AM Day: 18 Month: Nov. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" @ 4779 w/ 250 sq. cmt. w/ 2700' recovered. Perfs @ 4754-60. Bottom sand to 4700 w/ 4 sq. cmt. Pumpdown 4 1/2 w/ 3 sq. hulls, 15 sq. gel and 70 sq. 50/50 foamix, 4% gel-3% C.C.; then 1 sq. hulls, 15 sq. gel and release 4 1/2 plug; then 130 sq. foamix.

orders by J. Metz

Signed R. Barlutton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:00 AM Day: 18 Month: Nov. Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered. Max. pressure @ 600#, shut-in @ 200#. Cementing by Sun Oil (weel Cementing).

Remarks: 8 5/8" cemented w/ 375 sq and 4 1/2 cemented w/ 250 sq.

RECEIVED STATE CORPORATION COMMISSION NOV 19 1982 CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as stated and that I (did/ did not) observe this plugging.

DATE 11-24-82 INV. NO. 1723-4

Signed R. Barlutton (TECHNICIAN)