

To: 1 120350  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-5  
API NUMBER 15- 083-20,683 - 0000  
C NW NW, SEC. 32, T. 24 S, R 22 W/E  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5364  
Operator: Beren Corporation  
Name & Address: P.O. Box 723  
Hays, KS 67601

Lease Name Durler Well # 1  
County Hodgeman 154.73  
Well Total Depth 4761 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 418

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beren Corporation License Number 5364  
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 1 p.m. Day: 5 Month: 12 Year: 19 89

Plugging proposal received from George Juergenson  
(company name) Beren Corporation (phone) 913-628-6101

were: 5 1/2" at 4756' Perfs at 4732-40, 4745-49' Open hole at 4756-61' DV'd at 1497' w/450 sx  
1st plug pump 400 lbs. hulls and Thrifty Mix to fill,  
2nd plug pump 100 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 5 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 200 sx cement into 5 1/2" casing,  
Pumping pressure 0-1000 psi and shut in 800 psi.

2nd plug pumped 5 sx cement in 8 5/8" X 5 1/2" annulus. Pumping pressure 0-1000 psi and  
shut in 1000 psi.

12-12-89  
RECEIVED  
STATE CORPORATION COMMISSION  
666 12 1000

Remarks: Used light cement by B.J. Titan. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-13-89  
INV. NO. 26755  
12-5

Signed [Signature]  
(TECHNICIAN)