

1 060036

9-18
API NUMBER 15- 069-20,238 - 0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NE, SEC. 28, T 24 S, R 29 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104

Lease Name Hughes Well # 1

Operator: Blue Goose Drilling Company, Inc.
Name &

County Gray 163.63

Address P.O. Box 1413

Well Total Depth 5035 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 10 p.m. Day: 17 Month: 9 Year: 19 90

Plugging proposal received from Martin Miller

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1950-74' Elevation 2796'

1st plug at Arbuckle with 100 sx cement, 2nd plug at 1980' with 50 sx cement,

3rd plug at 1050' with 80 sx cement, 4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 a.m. Day: 18 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 5035' with 100 sx cement,

2nd plug at 1980' with 50 sx cement,

3rd plug at 1050' with 80 sx cement,

4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED

SEP 20 1990

9-20-90

CONSERVATION DIVISION
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. NOTE: LOG TOOL STUCK ON BOTTOM.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-25-90

Signed Cam Morris (TECHNICIAN)

INV. NO. 29401

9-18