

To: 1 090004
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- NA
C NW SW, SEC. 32, T 24 S, R 29 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317
Operator: Continental Energy
Name & Address: P.O. Box 918
Garden City, KS 67846

Lease Name Goddard Well # D-1
County Gray 166.69
Well Total Depth 5129 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Continental Energy License Number 5317

Address P.O. Box 918, Garden City, KS 67846

Company to plug at: Hour: 2:30 p.m. Day: 6 Month: 9 Year: 19 90

Plugging proposal received from Kevin Wiles

(company name) Continental Energy (phone) 316-276-8710

- were: 4 1/2" at 5123' w/200 sx cement, Perfs at 4778-82, 4762-66'
- 1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,
- 2nd plug pump 75 sx cement at 959',
- 3rd plug pump 5 sx gel and 50 sx cement at 430',
- 4th plug pump cement to top at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30 p.m. Day: 6 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dump 4 sx cement on top of sand through bailer.

2nd plug pumped 75 sx cement at 959',

3rd plug pulled to 430', pumped 5 sx gel and 50 sx cement,

4th plug pulled to 40', cemented to top.

Shut in pressure 85 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 960' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE: SEP 17 1990
INV. NO. 29324

SEP 11 1990

Signed Steve Middleton (TECHNICIAN)