

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-069-20, 182-0000

C NW-SE, Sec. 9, T 24 S, R 30 W 10

1980 feet from N(S) section line

1980 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License #5652

Lease Name Brown-F-G Prospect Well # 1

Operator: Mustang Drilling & Exploration County Gray

Name & Address 200 W. Douglas, #800
Wichita, Kans. 67202

Well Total Depth 5085 feet 165.26

Conductor Pipe: Size feet

Surface Casing: Size 8 1/2" feet 466

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration License Number 5652

Address P.O. Drawer 1609 Great Bend Kans 67530

Company to plug at: Hour 6:15 AM Day: 14 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Bill Nelson

(company name) Mustang Drilling & Exploration (phone)

were: 1st plug @ 1900' w/ 50 sbx cement.

2nd plug @ 960' w/ 50 sbx cement.

3rd plug @ 510' w/ 50 sbx cement.

4th plug @ 40' to 0' on solid bridge w/ 10 sbx cement.

Circulated 15 sbx cement in rat hole. Sum Cementing w/ 60/40 pps

w/ 27 gell & 3% CC.

Signed Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 8:15 AM Day: 14 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT

1st plug filled hole with heavy mud & pumped 50 sbx cement through drill pipe @ 1900'. 2nd plug w/ hole full of heavy mud pumped 50 sbx cement through drill pipe @ 960'. 3rd plug w/ hole full of heavy mud pumped 50 sbx cement through drill pipe @ 510'. 4th plug filled hole to 40' w/ heavy mud, dumped to sbx hulls & pushed rubber plug to 40' on solid bridge & pumped 10 sbx cement through drill pipe. 5th plug circulated 15 sbx cement through drill pipe in rat hole.

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 1-20-84

INV. NO. 9209 W

Signed Paul A. Luthie (TECHNICIAN)