

3-25-88

1 051029

API NUMBER 15- 069-20,226 -0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW, SEC. 15, T 24 S, R 30 W/E
1980 feet from S section line

TECHNICIAN'S PLUGGING REPORT

4620 feet from E section line

Operator License # 4569

Lease Name Wehkamp "A" Well # 1

Operator: Jay Boy Oil, Inc.

County Gray 165.75

Name & Address 535 Fourth Financial Center

Well Total Depth 5100 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 479

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 25 Month: 3 Year: 1988

Plugging proposal received from Don Kern

(company name) Allen Drilling Company (phone) 316-793-5681

Elevation 2832'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1958-81'

1st plug at 1970' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,

3rd plug at 510' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 25 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1970' with 50 sx cement,

2nd plug at 1000' with 80 sx cement,

3rd plug at 510' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 31 1988

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 4-5-88

INV. NO. 20290