

5-1-88

1 030942

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-069-20,118-6000

C SE NE, SEC. 16, T 24 S, R 30 W/EX
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4779

Lease Name Hall Well # 1

Operator: North American Resources Co.
Name & Address 16 East Granite
Butte, MT 59701

County Gray 165.85

Well Total Depth 5103 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 492

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Alfa Well Service License Number NA

Address NA

Company to plug at: Hour: 8 a.m. Day: 1 Month: 5 Year: 19 88

Plugging proposal received from Ted Mees

(company name) North American Resources Co. (phone) 406-259-9835

were: 4 1/2" at 5101' PRTD 5050' Perfs at 4828-38, 4852-62' Elevation 2841' GL Casing parted at 1537' KB

1st plug pump 4 1/2" with 2 sx hulls and 100 sx lite cement, followed by 40 sx Class H,

2nd plug pump 240 sx Class H cement down 8 5/8" annulus,

3rd plug pump 50 sx cement down 4 1/2"

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 9:45 a.m. Day: 1 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 4 1/2" with 2 sx hulls and 100 sx RFC (lite) cement followed by 40 sx Class H cement,

2nd plug pumped 240 sx Class H cement down 8 5/8" annulus, shut in w/500 lbs.,

3rd plug additional 50 sx pumped down 4 1/2" on vacuum.

Remarks: Used RFC (lite cement) and Class H cement by Dowell. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

RECEIVED
MAY 05 1988
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

Signed Steve Durrant (TECHNICIAN)

DATE 5-17-88

INV. NO. 20647