

1060179

TO: STATE CORPORATION COMMISSION

API NUMBER 15-069-20,269-0000  
70'S 40'W N/2 NW SEC. 16, T 24 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 730 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1280 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GATES WELL # A-16

TECHNICIAN'S PLUGGING REPORT

COUNTY GRAY

OPERATOR LICENSE # 4058

WELL TOTAL DEPTH 5070 FEET 16478

OPERATOR: AMERICAN WARRIOR PRODUCTION CSG: SIZE 5 1/2" @ 3226' WITH 435 SX

NAME AND PO BOX 399 SURFACE CASING: SIZE 8 5/8" @ 311' WITH 175 SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL,    GAS WELL,    X    INPUT WELL,    SWD WELL,    D/A   

OTHER WELL AS HEREINAFTER INDICATED   

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 08 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 2736-2642

BOTTOM PLUG 300# HULLS WITH CEMENT. PUMPED 220 SX CEMENT. PRESSURED TO 500#. SHUT IN WITH 500#. TIED ON BACKSIDE AND PUMPED 100 SX CEMENT. PRESSURED TO 480#. SHUT IN WITH 300#.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL    X    PART    NONE   

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 08 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT   

BOTTOM PLUG 300# HULLS AND CEMENT. PUMPED 220 SX CEMENT. PRESSURED TO 500#. SHUT IN WITH 500#. TIED ON TO BACKSIDE AND PUMPED 100 SX CEMENT. PRESSURED TO 480#. SHUT IN WITH 300#.

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1999 11-23-99

DATE 12-3

CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael Maier  
(TECHNICIAN)

FORM CP-2/3

*(Handwritten initials)*