

To: 1 090040  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-15 197 R  
API NUMBER 15- 069-20,241-0000  
App. C  
W/2 SW NW SEC. 19, T 24 S, R 30 W/2E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883  
Operator: Sharon Resources, Inc.  
Name & Address 5340 S. Quebec, Ste. 220  
Englewood, CO 80111

3180 feet from S section line  
4950 feet from E section line  
Lease Name Gates Well # 19-1  
County Gray 164.06  
Well Total Depth 5048 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302  
Address 1720 KSB & T Bldg., Wichita, KS 67202

Company to plug at: Hour: 9:30 p.m. Day: 14 Month: 1 Year: 19 91

Plugging proposal received from Rick Barringer  
(company name) Red Tiger Drilling Company (phone) 316-263-2371

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1962-2032'  
1st plug at 3100' with 100 sx cement, 2nd plug at 2032' with 50 sx cement,  
3rd plug at 980' with 80 sx cement, 4th plug at 490' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 12:45 a.m. Day: 15 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3100' with 100 sx cement,  
2nd plug at 2032' with 50 sx cement,  
3rd plug at 980' with 80 sx cement,  
4th plug at 490' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement, Water well filled with 15' sx cement.

Remarks: 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** PLEASE DO NOT observe this plugging.

DATE 2-13-91

INV. NO. 30728

Signed [Signature]  
(TECHNICIAN)