

To: 1 090802 4-12  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION of  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 083-21,441-0000  
100' S & 125' W  
W/2 SE NW, SEC. 4, T 24 S, R 23 W/E  
2080 feet from NS section line  
1525 feet from WE section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 7567

Lease Name Bradford Well # 1

Operator: Jack P. Bowles  
Name & Address  
P.O. Box 3285  
Edmond, OK 73083-3285

County Hodgeman 59.74

Well Total Depth 4915 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well Input Well SWD Well O&A X  
Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 12 Month: 4 Year: 1997

Plugging proposal received from Mike  
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1623'  
1st plug at 1630' with 50 sx cement, 2nd plug at 750' with 80 sx cement,  
3rd plug at 340' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 a.m. Day: 12 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 1630' with 50 sx cement,  
2nd plug at 750' with 80 sx cement, 4-17-97  
3rd plug at 340' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

INVOICED

DATE 4-17-97

Signed (TECHNICIAN)

MY NO. 47965

4-12 JUN 17 1997