

1 051120

1-13

API NUMBER 15- 083-21,261 - 0000

SW NW NW, SEC. 5, T 24 S, R 23 W/E

4290 feet from S section line

4950 feet from E section line

Lease Name Wolf Well # 1

County Hodgeman 153.99

Well Total Depth 4738 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 381

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation

Name & Address One Main Place, Suite 400

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Great Bend Casing Pullers Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 1 Year: 1989

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) 816-793-9711

were: 5 1/2" at 4731' w/75 sx cement Perfs at 4728-29' Open Hole at 4731-52' DV'd at 1631' w/290 sx cement

RECEIVED

STATE CORPORATION COMMISSION

1st plug pump 175 sx ATL and 4 sx hulls,

2nd plug pump 50 sx cement down backside.

JAN 18 1989 1-18-89

CONSERVATION DIVISION

Wichita, Kansas Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped 125 sx ATL down 5 1/2" casing, Maximum pressure 1500 psi Shut in 1500 psi,

2nd plug pumped 4 sx ATL down 5 1/2" X 8 5/8" annulus, Maximum pressure 500 psi and shut in 500 psi.

Remarks: Used ATL cement by Allied. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-20-89

INV. NO. 23739

Signed Richard W. Lacey (TECHNICIAN)