

1 070882

11-30

API NUMBER 19- 083-21,359-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NE, SEC. 6, T 24 S, R 23 W/E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Loose Name Wolf Trust "A" Well # 1

Operator: Pickrell Drilling Company, Inc.

County Hodgeman 156.00

Name & Address 110 N. Market, Suite 205

Well Total Depth 4800 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 30 Month: 11 Year: 19 90

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1600-37'

1st plug at 1650' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 p.m. Day: 30 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

DEC 4 1990

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(if additional description is necessary, use BACK of this form)

INVOICED

DATE 12-7-90

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 30193