

2 070107

SEP 20 1988

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NW, SEC. 28³⁰, T 27 S, R 10 WXR
feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Cunningham Well # B-8 SWD

Operator: Texaco, Inc., for Texaco Prod. Inc.
Name & Address: P.O. Box 2420
Tulsa, OK 74102

County Kingman
Well Total Depth 3476 feet
Conductor Pipe: Size 12-1/2" feet 321
Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Texaco License Number 4742
Address

Company to plug at: Hour: 8:30 Day: 6 Month: 9 Year: 1988

Plugging proposal received from Jack Luthi

(company name) (phone)

were: Sand bottom - 7 sx - run tubing to 1165' & bring cement to surface.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00 Day: 6 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT Sanded bottom from 3474' to 3352' - ran 7 sx of common from 3351' to 3314' - ran tubing to 2500' - 10 sx; 1st plug down at 10:00
Pulled tubing to 2000' - 10 sx - 2nd plug down @ 10:20
Pulled tubing to 1500' - 10 sx - 3rd plug down @ 11:00 - 60/40 2% gel

Pulled tubing to 1165' - pumped 160 sx - did not circulate - circulated about 25 bbl of oil and then quit. Pulled tubing - tied to back side and going to pump 75 sx of Thix-A-Tropic pressured to 500 lbs - did not fill. Tying to 12-1/2 surface pipe - pumping 60/40 2% gel & 5 hulls - 225 sx - 800 lbs pumping pressure - shot in at 200 lbs. Let well set over night - came back and ran 30 sx of 60/40 down 5-1/2 - filled to surface - tied back to 7" took 1 sx of 60/40 to pressure to 400 lbs. Back side stayed full.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

WK

Signed Jack Luthi (TECHNICIAN)