

To: 1 090844
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-069-20,265-8006
SE NE SE, SEC. 10, T 24 S, R 30 W/8
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Hands Well # 1

Operator: Knighton Oil Company, Inc.
Name & Address: 221 S. Broadway, Ste. 710
Wichita, KS 67202

County Gray 160.45
Well Total Depth 4937 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: Day: 6 Month: 9 Year: 19 97

Plugging proposal received from Walter Brown

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2044'.

- 1st plug at 2045' with 50 sx cement, 2nd plug at 1030' with 80 sx cement,
- 3rd plug at 550' with 40 sx cement, 4th plug at 260' with 40 sx cement,
- 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:45 a.m. Day: 6 Month: 9 Year: 19 97

- ACTUAL PLUGGING REPORT 1st plug at 2045' with 50 sx cement,
- 2nd plug at 1030' with 80 sx cement,
- 3rd plug at 550' with 40 sx cement,
- 4th plug at 260' with 40 sx cement,
- 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 9-11-97
INV. NO. 48968
9-6

Signed [Signature] (TECHNICIAN)

RECEIVED
SEP 11 1997
D 1:20