

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21407-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 35-23S-4W
1320 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: GORDON SCHMIDT Well Number: 1
County: RENO Total Vertical Depth: 3361 feet

Operator License No.: 5330 Conductor Pipe: Size 13.375 feet: 284
Op Name: EXCALIBUR PRODUCTION COMPANY, Surface Casing: Size 8.625 feet: 604 300 sx cmt
Address: PO BOX 278 1016 N. MAIN Production: Size 5.5 feet: 3349 100 sx cmt
MCPHERSON, KS 67460 Liner: Size feet:
8109.23

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/18/2001 1:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS GORDLEY Company: EXCALIBUR PRODUCTION CO. IN Phone: (316) 242-7156

Proposed Plugging Method: Fill with sand to 3290 spot 10 sx cmt. on sand. Pull pipe from 2700', 35 x at 900, 35 sx at 654, fill with cmt. from 315' to surface.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 09/18/2001 5:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,290' and topped with 5 sxs. cement. Shot 5 1/2" casing off at 2,000'. Pulled casing to 666' and spotted 50 sxs. cement. Pulled casing to 344' and circulated 115 sxs. cement to the surface. Topped off with 35 sxs. cement on 09/21/01.

RECEIVED
KCC DISTRICT #2

SEP 26 2001

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% EGL BY COPELAND ACID & CEMENTING. INVOICE #20805.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 10-01-01

INV. NO. 2002060685