

2030335

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-20, 986-0000

E/2 SE SW 1/4 SEC. 35, T 23 S, R 4 W 1/4

1980 feet from N/S section line

2970' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5284 - # 8110

Lease Name Brandenberger Well # 1

Operator: Hiebert + Wedel

County Reno 110.50

Name: Hiebert + Wedel

Well Total Depth 3400' PBT.D 3370' feet

Address 1136 Wheeler, Box 785

~~Surface~~ Pipe: Size 5 1/2" feet 3398'

McPherson, Ks. 67460

Surface Casing: Size 12 3/4" feet 248'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 14:30 Day: 13 Month: 12 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Perfs. 3275' to 3357' Sand hole to 3225', dump 6 ex. cent., shoot and pull 5 1/2" casing, pump 3 ex. balls, 15 ex. gel, 140 ex. cent. down 12 3/4" casing.

Plugging Proposal Received by Dist # 2
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 15:30 Day: 13 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT Sanded hole to 3225' dumped 6 ex. cent.

with bailer, shot and pulled 2948' of 5 1/2" casing.

Halliburton Services # 099812-X pumped 3 ex. balls,

15 ex. gel, 160 ex. 60-40 Permiox cent. down 12 3/4" cas. cas.

Pump Press 100 # L.P. 50 #

Remarks: Top Plug
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-7-86
INV. NO. 11871

RECEIVED
STATE CORPORATION COMMISSION
1-6-86
JAN 6 1986
Conservation Division
Wichita, Kansas

Signed Don Thompson
(TECHNICIAN)
RC
FORM CP-2/3
Rev. 01-84