



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rowe of Slawson has this

date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408-120 Bldg., Wichita, Kansas

Lease Name: Mooney "E" Well No. 1

Location: C SW NW Sec. 18 Twp. 24 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4790' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rowe was instructed to plug the well as follows:

8 5/8" to 397' circulated w/ cement. Mud 4790' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 390'

Spot 35 sacks cement 390' to 290' Mud 290' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent