

State of Kansas



15-095-01504-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

15-095-01504-0000

Mr. Bill Wood of Texaco Oil Co. Inc. has this

date requested permission to plug the following described well:

Mr. Wood guarantees payment of the plugging fee.

Operator's full Name: Texaco Oil Co. Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Pieplow-Campbell Well No. # 1

Location: C NW ~~NE~~ SE Sec. 33 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 3756 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wood was instructed to plug the well as follows:

204' of 8 5/8" surface pipe cement circulated with 200 sacks.

Fill hole with heavy mud to 180', 1st cementing plug,

1/2 sack hulls, cement with 20 sacks. Fill hole with mud to

40', 2nd cementing plug, 1/2 sack hulls, cement with 10 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent