



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Burton of Pickrell Drlg. Co. has this  
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 705 4th Natl Bldg. Wichita, Ks

Lease Name: Richardson E Well No. 1

Location: C SW/NW Sec. 36 Twp. 29s Rge. 6 (E)(W) W

County: Kingman Total Depth 4535 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burton was instructed to plug the well as follows:  
228 ft 8 5/8 surface pipe cemented with 160 sacks. Fill hole  
to 210 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud to  
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.  
2 sacks cement in rat hole.

Very truly yours,

Russell Biberstein  
Conservation Division Agent