

15-095-20001-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
JAN 17 1967
01-17-67
CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill, filed
January 16, 1967

Dear Sir:

Mr. Red Bishop of Leben Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Bock Well No. # 1

Location: C SW NE Sec. 17 Twp. 29 Rge. 8 (E)(W) W

County Kingman County Total Depth 4560 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

208' of 8 5/8" surface pipe, cement circulated with 150 sacks. Fill
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack
hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent