

State of Kansas



15-095-20022-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed April 25, 1967.

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks. 67202

Lease Name: Young "D" Well No. # 2

Location: C NE NW Sec. 23 Twp. 29 Rge. 8 (E)(W) W

County Kingman Total Depth 4274' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cement circulated with 165 sacks. Fill
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1967
DS-05-67
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Archie Elving
Conservation Division Agent