

State of Kansas



15-095-20512-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)STATE CORPORATION COM.
09-28-76
SEP 20 1973CONSERVATION DIVISION
WICHITA, KANSASJ. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Co has this
date requested permission to plug the following described well:Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Keener Oil CoComplete Address: 406 Natl Bank Bldg of Tulsa Tulsa, OKLease Name: Lantha Young Well No. 1Location: 40' E SW/NE Sec. 23 Twp. 29s Rge. 8 (E)(W) County: Kingman Total Depth 4212 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cameron was instructed to plug the well as follows:202 ft 8 5/8 surface cemented with 175 sacks. Pump plug,35 sacks cement to 190 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 5 sacks cement inrat hole.Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent