

15-095-30243-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1966  
06-13-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Kaufman "B" Well No. # 1

Location C SE SE Sec. 7 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4197'

Abandoned Oil Well ~~Oil~~ Gas Well        Input Well        SWD Well        D & A X ANB

Other well as hereafter indicated:       

Plugging Contractor: Winfield Oil Field Service, Inc.

Address: Box 952, Winfield, Kansas License No. 531

Operation Completed: Hour 3:00PM Day 6th Month June Year 1966

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cemented with 155 sacks. 4196' of 4 1/2" long  
string, cemented with 150 sacks. Plug back T.D. 4143'. Top perforation  
4112'. 25 sacks of cement was pumped into the perforations, bringing the  
top of the cement to 3753'. 3501' of 4 1/2" long string was recovered from  
the hole. Hole was filled with mud to 200', rock bridge from 200' from  
200' to 190', and cemented with 25 sacks. Hole was filled with mud to  
40', rock bridge from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/13/66  
INV. NO. 3384-11

Signed: Audrie Elving  
Well Plugging Supervisor