

15-095-20008-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas 67530

Lease Name Stucky Well No. # 1

Location NW NE NW Sec. 31 Twp. 29 Rge. 5 (E) (W) W

County Kingman Total Depth 4557'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10:30 AM Day 22nd Month November Year 1967

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cemented with 200 sacks. 4552' of 5 1/2" long string,  
cemented with 100 sacks. Top perforation 4497'. Bottom of the hole was sanded  
to 4490', and cemented with 5 sacks, through the dump bailer. 3915' of 5 1/2"  
long string was recovered from the hole. Hole was filled with mud to 250',  
rock bridge from 250' to 240', and cemented with 25 sacks, with cement from  
240' to 165'. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 11-28-67

INV. NO. 6755-W