

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1977
10-25-1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 069 - 20017 - 0000 (6-8535)
Wichita, KS (for this well)

Operator's Full Name Gear Petroleum Company

Complete Address 1325 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Leon Brady "C" Well No. 1

Location NW NW NW Sec. 6 Twp. 24 Rge. (E) (W) 28

County Gray Total Depth 5100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor T-Bird Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 3:15 A Day 20 Month 10 Year 1977

The above well was plugged as follows:

RTD 5100' 8 5/8 csg set 410' cwc 250 sk. Plg. Mat. "Common"

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-28-77

INV. NO. 6089-W