

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 083 - 20,573 - 0000 (this well)

RECEIVED
STATE CORPORATION COMMISSION
JAN 03 1978
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson
Complete Address 200 Douglas Bldg., Wichita, Kansas
Lease Name Nielson "G" Well No. 1
Location Appx. C NE Sec. 5 Twp. 24 Rge. (E) (W) 22
County Hodgeman Total Depth 4735'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools

Address License No.
Operation Completed: Hour 4:20 P Day 30 Month 12 Year 1977

The above well was plugged as follows:
RTD 4735' 8 5/8 csg set 321' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 300' sets 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 1-4-78
INV. NO. 6496W