

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County. Sec. 30 Twp. 24S Rge. 22W EA
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
C-W/2 NE NE


Lease Owner Jack Bowles
Lease Name Eining Well No. 1
Office Address 101 Park Avenue, Suite 1230, OK City, OK
Character of Well (Completed as Oil, Gas or Dry Hole) 73102
Dry Hole

Date Well completed November 26, 1979
Application for plugging filed Verbal Application 1979
Application for plugging approved Verbal Approval 1979
Plugging commenced November 26, 1979
Plugging completed November 26, 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1979

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,835'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	336'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,835 ft. (rotary total depth) to 900 ft. Set plug at 900 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 900 ft. to 330 ft. Set plug at 330 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 330 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick
Dean Britting, Agent (Signature of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1979

My commission expires July 25, 1982

Elsie Willison
Elsie Willison - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
12-4-79
CONSERVATION DIVISION



KANSAS DRILLERS LOG

COMPANY Jack Bowles

SEC. 30 T. 24S R. 22W

FARM Eining NO. 1

LOC. C-W/2 NE NE

COUNTY Hodgeman

ROTARY TOTAL DEPTH 4,835'

COMM. November 16, 1979 COMP. November 26, 1979

CONTRACTOR H-30, Inc. (Rig #2)

ISSUED December 3, 1979

CASING

10 3/4"

8 5/8" Set at 336' cemented w/210 sxs cement

ELEVATION 2,346' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	200'
Shale and Shells	338'
Shale	970'
Sand	1,090'
Shale	1,481'
Anhydrite	1,519'
Shale and Lime	1,810'
Shale and Sand	2,285'
Shale and Lime	2,850'
Lime and Shale	3,280'
Shale and Lime	3,662'
Lime and Shale	3,800'
Shale and Lime	4,000'
Lime and Shale	4,320'
Lime	4,835'
Rotary Total Depth	4,835'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of December, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

DEC - 4 1979

CONSERVATION DIVISION
Wichita, Kansas