

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 36 Twp. 24S Rge. 22W(E) (W)
C SW NE

Location as "NE/CNW*SW*W*" or footage from lines _____

Lease Owner Imperial Oil Company

Lease Name MEAD Well No. 1

Office Address 780 Fourth Natl. Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/9/62 19

Application for plugging filed 9/9/62 19

Application for plugging approved 9/9/62 19

Plugging commenced 9/9/62 19


Plugging completed 9/9/62 19

Reason for abandonment of well or producing formation _____

No commercial quantities of oil found

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Liberal

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4862 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	8-5/8"	at 258'	not pulled		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 550' with 20 sacks cement

Set second plug at 250' with 15 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1962

9-21-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address Box 97, WaKeeney, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
John Lehman (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman

780 Fourth Natl. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 1962

My commission expires July 5, 1966

Bette J. Silcott
Bette J. Silcott Notary Public.



DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

MEAD NO. 1
C SW NE Sec. 36-24S-22W
Hodgeman County, Kansas

Total Depth: 4862'

Commenced: 8/26/52 Completed 9/9/62

Elevation: 2357 K.B.
Production: dry

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8 " surface pipe at 258' with 200 sacks cement

Figures indicate bottom of formations:

		<u>TOPS</u>	
Sand and Shale	100'	Heebner	4016 (-1659)
Shale	258'	Toronto	4030 (-1673)
Shale & Sand	1375'	Brown Lime	4111 (-1754)
Anhydrite	1385'	Lansing-Kansas City	4122 (-1765)
Shale & Sand	1490'	Base Kansas City	4494 (-2137)
Shale	1765'	Cherokee Shale	4647 (-2290)
Shale & Shells	2185'	Conglomerate	4711 (-2354)
Shale & Lime	4060'	Mississippi (Osage)	4752 (-2395)
Lime	4755'	Kinderhook	4845 (-2488)
Lime & Chert	4833'	Rotary Total Depth	4862 (-2505)
Chert	4865'		

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1962
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

BY Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 20th day of September 1962.

My Commission Expires:

July 5, 1966

Bette J. Silcott
Bette J. Silcott, Notary Public