

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 36 Twp. 24 Rge. 22 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C NE NW  
Lease Owner Palomino Petroleum  
Lease Name Hoffman Well No. 1  
Office Address 304 Insurance Bldg. Wichita, Kans. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed January 13 1972  
Application for plugging filed February 15 1973  
Application for plugging approved February 16 1973  
Plugging commenced 3/7 1973  
Plugging completed 3/21 1973  
Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production December 6 1972  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves  
Producing formation Cherokee Lime Depth to top 4680 Bottom 4700 Total Depth of Well 4765 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	331'	
				5 1/2"	4760'	2701'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Set plug at 4175'. Filled with sand from 4175' to 4150'.  
Run 5 sacks cement from 4150' to 4120'.  
Pumped 5 sacks mud, 80 sacks cement, 3 sacks mud, 30 sacks cement, 2 sacks mud & 15 sacks cement to plug well.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn's Pipe Pulling Co.  
Address Box 156 Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Sedgwick ss.  
R. W. Watchous (employer/lessee) of (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
R. W. Watchous

304 Insurance Bldg. Wichita, Kansas 67202

to before me this 23rd day of March, 19 73  
Celia A. Smith  
Celia A. Smith Notary Public.



My commission expires October 8, 1976

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1973  
CONSERVATION DIVISION  
Wichita, Kansas

HOFFMAN #1  
NE NW, Sec. 36-24S-22W  
Hodgeman County, Kansas

Commenced: October 11, 1971  
Completed: October 26, 1971

Operator: Beardmore Oil, Inc.

Depth		Formation	Remarks
From	To		
0	250	Top soil - sand - shale	Ran 8 jts of used 24# 8 5/8"
250	331	Sand and shale	csg set @ 331' w/200 sks common
331	975	Shale	2% Gel 3% CC
975	1095	Sand	P.D. @ 7 PM 10/11/71
1095	1480	Shale	Cement Circ. Job by Globe
1480	1505	Anhydrite	
1505	1545	Shale w/lime stks	
1545	1960	Shale and shells	
1960	2330	Shale w/lime stks	
2330	2490	Shale and lime	
2490	2730	Lime and shale	
2730	2825	Lime	
2825	2985	Lime and shale	
2985	3125	Shale and lime	
3125	4184	Lime and shale	
4184	4360	Lime	Ran 137 jts of used 5 1/2" csg.
4360	4443	Lime and shale	14# set @ 4660 w/150 sks salt
4443	4765	Lime	sat w/1/4# Nylon per sack
4765	TD		P.D. 9 AM 10/26/1971 Job by Howco

4760

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the NE NW, Section 36-24S-22W, Hodgeman County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
James S. Sutton II

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 1st day of November, 1971, personally appeared James S. Sutton II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Marjorie Hall*  
Marjorie Hall, Notary Public



My commission expires Nov. 29, 1971