

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER OWWO

LEASE NAME Kramer

WELL NUMBER 1

SPOT LOCATION C-NE-SE

SEC. 31 TWP. 24 RGE. 29 (E) (W)

COUNTY Gray

Date Well ^{approx.} Completed 2/27/81

Plugging Commenced 2-2-1988

Plugging Completed 2-9-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Continental Energy

ADDRESS 906 S. Highway 83, Frontage Rd.
Garden City, Ks. 67846

PHONE # (314) 276-8710 OPERATORS LICENSE NO. 5317

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation St. Louis Depth to top 4900' bottom 4910' T.D. 5100'

Show depth and thickness of all water, oil and gas formations.

2-19-88

RECEIVED

OIL, GAS OR WATER RECORDS | CASING RECORD | STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	364'	0'
Production				4 1/2"	5100'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 25 sks. cement to 4650'
 Mud 4650' to 1940' - Pump 40 sks. cement 1940' to 1840'
 Mud 1840' to 930' - Pump 50 sks. cement 930' to 830'
 Mud 830' to 390' - Pump 40 sks. cement 390' to 290'
 Mud 290' to 40' - put bridge & 10 sks. cement 40' to 3'
 Cut off 8 5/8", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

Edgar J. Eves

(~~Operator~~) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 10 day of Feb., 19 88

Sandra L. Eves
Notary Public

My Commission expires: 12-6-88

