

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-069-20160-0000

LEASE NAME Goddard

WELL NUMBER "D" 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 32 TWP. 24 RGE. 29 (E or W)

COUNTY Gray

Date Well Completed N/A

Plugging Commenced 9-4-90

Plugging Completed 9-6-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Continental Energy

ADDRESS P. O. Box 918 Garden City, KS 67846

PHONE# (316) 276-8710 OPERATORS LICENSE NO. 5317

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS
bought well

Is ACO-1 filed? no info: If not, is well log attached?

Producing Formation St. Louis Depth to Top Bottom T.D. 5129

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>N/A</u>				<u>8 5/8"</u>	<u>415</u>	<u>959' of</u>
				<u>4 1/2"</u>	<u>5123</u>	<u>4 1/2 9/5# casing</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded up to 4700'. Dump 4 sacks cement thru bailer on top. Shot pipe free @ 959'. pump 5 sacks gel and 75 sacks 60/40 POZ 6% gel, 1/4" Flocele per sack; pull casing to 430'. pump 5 sacks gel, and 50 sacks 60/40 POZ 6% gel. Pull pipe to 40' pump 10 sacks @ 40' to surface.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Continental Energy License No. 5317

Address P. O. Box 918 Garden City, KS

STATE OF Kansas COUNTY OF Finney, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Kevin Miles

(Address) P. O. Box 918 G C KS 67846

SUBSCRIBED AND SWORN TO before me this 7 day of September, 19 90

RECEIVED
STATE CORPORATION COMMISSION
9-11-90

Paula S. Elliott
Notary Public

SMC Com 1990 Expires: 11-30-93