

2 100161

-155-20985-0000  
5-4-84

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
SW/4, SEC. 35, T 23 S, R 4 WXX

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ 330 feet from S section line  
\_\_\_\_\_ 3630 feet from E section line

Operator License # 5330

Lease Name Brandenberger Well # 1

Operator: Excalibur Production Co., Inc.  
Name & Address Box 278  
McPherson, KS 67460

County Reno 109.14

Well Total Depth 3358 feet

~~CONDUCTOR~~ Pipe: Size 5 1/2 feet 3356

Surface Casing: Size 8 5/8 feet 584 - 250 sks.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated perf 3332-3338'

Plugging Contractor Gressel Oilfield Service License Number 3004

Address Box 607, Burrton, KS 67020

Company to plug at: Hour: 1 p.m. Day: 16 Month: 9 Year: 19 86

Plugging proposal received from Ed Gressel

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: sand bottom 50 feet over perms - dump 5 sacks of cement - shoot 5 1/2" - pull  
pipe - bridge at 350' - fill with redi-mix

Plugging Proposal Received by District 2  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 pm. Day: 19 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT Sanded to 3280 feet and dumped 5 sacks of cement. Shot 5 1/2"  
and pulled 62 joints. Built bridge 25' at 350 feet and filled with redi-mix to  
surface. Capped well with metal plate.

Rec'd  
9-30-86

Remarks: Haven Redi-mix 3 1/2 yards  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-30-86  
INV. NO. 15028

observe this plugging.  
Signed J.L. Sanders  
(TECHNICIAN)