

1 080567

Plugged 11-16-86 75
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,264-0000
Approx. C
N/2 NE NW SEC. 16, T 24 S, R 23 W/E

4950 feet from S section line
3350 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Fagen Well # 1

Operator: Viking Resources

County Hodgeman 153.40

Name & Address 217 E. William

Well Total Depth 4720 feet

Wichita, KS 67202-4005

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Inc. License Number 5420

Address Box 1586, Great Bend, KS 67530

Company to plug at: Hour: 7 a.m. Day: 16 Month: 11 Year: 19 86

Plugging proposal received from Steve Colcogne

(company name) White & Ellis Drilling Inc. (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1580'

1st plug at 1580' with 40 sx cement, 2nd plug at 750' with 50 sx cement,

3rd plug at 290' with 50 sx cement, 4th plug at 0-40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 a.m. Day: 16 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1580' with 40 sx cement,

2nd plug at 750' with 50 sx cement,

3rd plug at 290' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

DATE 11-21-86

Signed J. R. [Signature]
(TECHNICIAN)

INV. NO. 15402