

2 030388

15-155.03202-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 8-14-1934

CNW SW, SEC. 36, T 23 S, R 4 W

1980' feet from S section line

4620' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Lease Name Bughman Well # 1

Operator: BHP Petroleum (Americas) Inc.

County Reno 109.40

Name & Address 925 Patton Road

Well Total Depth 3366' feet

Great Bend, Ks. 67530

~~Casing~~ Pipe: Size 7" feet 3258'/100sx

Surface Casing: Size 20" feet 234' cement to sur.  
5 1/2" line 3255' to 3326'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Ks. 67530

Company to plug at: Hour: 11:00 Day: 28 Month: 3 Year: 19 86

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: tubing stub 2467, push plug, sand, dump. 10 sq cent.

Bridge 7" cas. 400', shot cas. 300', circ. cement. to surface.

RECEIVED  
STATE CORPORATION COMMISSION

APR 4 1986  
4-11-86

Plugging Proposal Received by Don Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 14:30 Day: 28 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Pushed plug. to 2453', sand to 2400', dumped 10 sq cent.

with trailer, Built Bridge 580' to 530', Shot 7" casing at 300'

United Cementing # 0810 pumped 250 ex Premix 67ozel + 250 sq Ch.A.

cent down 7" casing, cement circ. to surface, shut well in.

Pump Press 400' L.L.P. 0#

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

(did)  (did not) observe this plugging.

DATE APR 11 1986

INV. NO. 13377

Signed Don Thompson  
(TECHNICIAN)