

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-03164-00-00
Spot: NWNENE Sec/Twnshp/Rge: 36-23S-4W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: SMITH Well Number: 3
County: RENO Total Vertical Depth: 3338 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

Production Casing Size: 5.5 feet: 3302 150 sxs.
Surface Casing Size: 10.75 feet: 260 240 sxs. *#108⁴⁹*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2003 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: DAVID WILSON Company: KAHAN & ASSOCIATES, INC. Phone: (918) 492-9797

Proposed Plugging Method: Sand to 3,250' and top with 5 sxs. cement. Perforate 5 1/5" casing at 600' and 310'. Run tubing to 600' and spot 35 sxs. cement. Pull tubing to 310' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/19/2003 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,020' and topped with 5 sxs. cement. Perforated 5 1/2" casing at 600'. Ran 2 3/8" tubing to 600', spotted 35 sxs. cement, and pulled tubing. Ran 2 3/8" tubing to down 10 3/4" & 5 1/2" annulus and circulated 165 sxs. cement to the surface. Ran 2 3/8", inside 5 1/2" casing, tubing to 400' and tagged top of cement. Pulled tubing to 310' and circulated 49 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2003
WICHITA, KS
RECEIVED
KCC DISTRICT #2
OCT 20 2003
WICHITA, KS
CONSERVATION DIVISION
WICHITA, KS
10-22-03

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE # 4783.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 10-22-03
INV. NO. 2004060655