

10-24

2-100640

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-155-02846-0000

API NUMBER: 10/26/34

SE NW, SECTION 36 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 30385 FEET FROM S SECTION LINE _____
FEET FROM E SECTION LINE _____

OPERATOR Liedtke Partners
NAME & P. O. Box 1605
ADDRESS Great Bend, KS 67530

LEASE NAME: Stalcup #2

COUNTY: Reno

WELL TOTAL DEPTH: 3360' PBTD/3375'

CONDUCTOR PIPE: 8-5/8" @ 3365'

SURFACE CASING: 16" @ 233' 109.68

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: Perf 3338-3306'

PLUGGING CONTRACTOR: Great Bend Casing Pullers, Inc.
ADDRESS: Great Bend, KS 67530 LICENSE: 4635

COMPANY TO PLUG AT: HOUR: 2:00p DAY: 19 MONTH: 10 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Richard Tennant
COMPANY NAME: Liedtke Partners PHONE: _____

WERE: Run tubing to bottom - 50 sx at 3200' - pull tubing to 650' - circ inside and outside 8-5/8" w/50 sx cmt - pull pipe to 350' - circ inside & outside 8-5/8" to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 2:00a DAY: 24 MONTH: 10 YEAR: 1990

ACTUAL PLUGGING REPORT:
Shot pipe off at 650' and 350' - tired to run tub to bottom - got stuck at 650' - drilled well at 657' and circ 45 vis mud - sand and rock fell in - had to pull out - bullhead squeeze & circ backside 350' to surface w/250 sx - drilled cmt to 375' to 460' and broke thru iron at 660' - ran tub to 3200' & circ mud 20 min - followed by 50 sx cmt - pulled tub to 689' & circ 50 sx cmt inside and outside 8-5/8" - pulled tub to 377' & circ to surface.

11-5-90

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: B. J. Titan #609488 & #609493 60/40 4% gel 500 sx NOV 5 1990

CONSERVATION DIVISION
Wichita, Kansas

I DID OBSERVE THIS PLUGGING.
INVOICED

DATE 11-13-90

John Sanders
John Sanders (AGENT)

INV. NO. 29929

FORM CP-2/3
REV. 3/90