

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21744-00-00
Spot: CW2E2SE Sec/Twnshp/Rge: 21-29S-7W
1465 feet from S Section Line, 1070 feet from E Section Line
Lease/Unit Name: GRABER B Well Number: 1
County: KINGMAN Total Vertical Depth: 4247 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 275 175 SX CMT
Production: Size 4.5 feet: 4247 125 SX CMT 138.23
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/29/2001 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (316) 727-3410

Proposed Plugging Method: Sand to 4090' and 4sxs cement. 35sxs @ 1100'. 35sxs @ 700'. Circulated cement from 307'.

Plugging Proposal Received By: JACK LUTHI

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/02/2001 5:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The hole was sanded back to 4090' and capped w/4sxs of cement. The casing was recovered from 3031', and pulled to 1100', where 35sxs of cement was spotted. The casing was pulled to 700', where 35sxs of cement was spotted. The casing was pulled to 700', where cement was circulated to surface. The remaining pipe was pulled, and the cement was topped off.

INVOICED INVOICED

RECEIVED
KCC DISTRICT #2

APR 16 2001

WICHITA, KS

INVOICED

DATE 4-17-01

INV. NO. 2001061675

Remarks: UNITED CEMENTING 60/40 POZ

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)