

8-14

2-040891

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-095-00828-0000

NE SW SE , SECTION 30 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 8759 990 FEET FROM S SECTION LINE
OPERATOR MACK ENERGY COMPANY 1650 FEET FROM E SECTION LINE
NAME & P.O. BOX 400
ADDRESS DUNCAN, OK 73534

LEASE NAME: WILSON #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4230' 137.48
PIPE: 4 1/2" @ 4229'
SURFACE CASING: 8 5/8" @ 280'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: _____

WERE: SAND TO 4050' AND 4 SACKS
35 SACKS AT 1150'
35 SACKS AT 700'
CIRCULATE 320' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }


COMPLETED: HOUR: _____ DAY: 14 MONTH: 8 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND, 4206' TO 4080' AND 4 SACKS.
THE 4 1/2" WAS RECOVERED FROM 3700' AND PULLED TO 1142' WHERE 35 SACKS OF
CEMENT WAS SPOTTED. 4 1/2" PULLED TO 684', SPOTTED 35 SACKS OF CEMENT.
4 1/2" PULLED TO 320', CIRCULATED CEMENT TO SURFACE. 4 1/2" PULLED AND
CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.



STEVE VAN GIESON

SEP 11 1997

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 9-11-97

INV. NO. 48971

8-14