

2 040428

7-15-88

API NUMBER 15-095-21565-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SE, SEC. 32, T 29 S, R 7 W/EX

1980 feet from S section line

1980 feet from E section line

Lease Name Brand Well # 1-32

County Kingman 139.26

Well Total Depth 4285 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 214.50

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Operator: Pratt Well Service

Name & Address Box 847

Pratt, KS 67124

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Pratt, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Ken Gates

(company name) Pratt Well Service (phone)

were: Perf. 4210-16 sand to 3992 and 5 sks.

4183-89 Rec. 2591

4168-73

4160-63 5 1/2 4281

Plugging Proposal Received by John Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1520 Day: 15 Month: July Year: 19 88

ACTUAL PLUGGING REPORT The perforations were covered with 5sks of cement. The 5 1/2

was shot off and recovered from 2591'. The remaining hole was squeezed plugged

by pumping through a swedge 250# of hulls, 12 sks of gel and 100 sks of 60/40 Poz-Mix

cement 4% gel.

07-20-88

Remarks: Howco 415865 mx600# SI 250# 60/40 4% gel

(If additional description is necessary, use BACK of this form.)

I (did) (did not) observe this plugging.

DATE 7-26-88

Signed Steve Van Dusen (TECHNICIAN)

INV. NO. 21671

7-15