

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19018-00-00
Spot: NENWNE Sec/Twnshp/Rge: 33-29S-7W
4950 feet from S Section Line, 1570 feet from E Section Line
Lease/Unit Name: BIRKENBAUGH B Well Number: 2
County: KINGMAN Total Vertical Depth: 4285 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

Conductor Pipe: Size feet: \$139.26
Surface Casing: Size 8.625 feet: 246 110 SX CMT
Production: Size 5.5 feet: 4285 115 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/13/2002 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 793-2316

Proposed
Plugging
Method:

Perfs. 4180'-4190'. Sand to 4130' and 5sxs of cement. 35sxs @ 1100'. 35sxs @ 700'. Circulate cement from 290'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 02/13/2002 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand from 4252'-4130' and capped w/5sxs of cement. The casing was recovered from 2841', and pulled to 110', where 35sxs of cement was spotted in place. The casing was pulled to 700', where 35sxs of cement was spotted. The casing was pulled to 300', where cement was circulated to surface. The remaining casing was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2

FEB 14 2002


WICHITA, KS

Remarks: ALLIED CEMENTING COMMON CEMENT.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE Feb 20-02

INV. NO. 2002061400