

7-23

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-095-19043-0000

CEL SW NW, SECTION 33 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 5134 3300 FEET FROM S SECTION LINE  
4290 FEET FROM E SECTION LINE

OPERATOR Graham Michaelis Corp.  
NAME & P.O Box 247  
ADDRESS Wichita, KS 67201

RECEIVED  
KANSAS CORPORATION COMMISSION

LEASE NAME: Campbell #B-3

COUNTY: Kingman 138.12

WELL TOTAL DEPTH: 4250(4208)

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 243'

JUL 27 1993  
07-27-93  
CONSERVATION DIVISION  
WICHITA, KS

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.

ADDRESS: P.O. Box 347 Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 23 MONTH: 7 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Dave Patterson

COMPANY NAME: Graham-Michaelis Corp. PHONE: 405-256-6491

WERE: Sand to 4120' and top w/ 5sx cmt- shoot off pipe and spot 35sx @ 1300', 35sx @ 800'- and circ cmt from 300' to the surface. Perf 4170' to 4179', 5-1/2" @ 4249'

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:15 DAY: 23 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded to 4120' and topped with 5sx cmt- shot pipe off at 3018'- pulled pipe to 1125'and pumped 35 sx cmt- pulled pipe to 700' and spotted 35sx cmt- pulled pipe to 300' and circ 95sx cmt to the surface. Recovered 3018' of 5-1/2" casing

REMARKS: Used 60/40 poz w/ 4% gel by Allied #2786

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Michael R. Wilson (AGENT)

INVOICED

DATE AUG 04 1993

INV. NO. 38249