

Original

RECEIVED  
KANSAS CORPORATION COMMISSION

12-30

2-

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

FEB 10 1994

API NUMBER: N/A 15-095-19044-0000  
SE NW NW, SECTION 33 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 5134

4290 FEET FROM S SECTION LINE  
4290 FEET FROM E SECTION LINE

OPERATOR GRAHAM MICHALIS CORP  
NAME & P O BOX 769  
ADDRESS WOODWARD OK 73801

LEASE NAME: CAMPBELL A-2  
COUNTY: KINGMAN  
WELL TOTAL DEPTH: 4255'

PIPE: 5-1/2" @ 4253' 138.22

SURFACE CASING: 8-5/8" @ 245'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: KELSO CASING PULLING  
ADDRESS: CHASE, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DARRELL KELSO

COMPANY NAME: KELSO CASING PHONE: \_\_\_\_\_

WERE: SAND TO 4200' & 5 SX - 1150' 35 SX - 700' 35 SX -  
295' CIRC CMT OH 4253'-4255'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 12:00 DAY: 30 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:  
BTM SANDED BACK TO 4114' & CAPPED W/5 SX CMT -  
4-1/2" FRM 3027' & PULLED TO 1135' & 35 SX CMT SPTD  
- PIPE PULLED TO 694' & 35 SX CMT SPOTTED - PIPE PULLED  
TO 300' & CMT CIRC TO SURF - REMAINING PIPE PULLED FRM  
WELLBORE & CMT FILLED TO SURF

REMARKS: ALLIED #3676 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson (AGENT)

DATE FEB 11 1994

INV. NO. 39914