

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00590-00-00
Spot: C Sec/Twnshp/Rge: 17-26S-38W
2640 feet from N Section Line, 2640 feet from E Section Line
Lease/Unit Name: JOHNSTON Well Number: 1
County: KEARNY Total Vertical Depth: 2676 feet

Operator License No.: 5952 Conductor Pipe: Size _____ feet: 886.97
Op Name: BP AMERICA PRODUCTION COMPANY Surface Casing: Size 10.75 feet: 646 WITH 425 SX CMT
Address: 2225 WEST OKLAHOMA AVENUE Production: Size 7 feet: 2465 WITH 350 SX CMT
ULYSSES, KS 67880 Liner: Size 4.5 feet: 2400 WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/10/2002 9:30 AM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: CARY SPOHN Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: FILL CASING TOP TO BOTTOM. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/10/2002 11:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

SLOTTED LINER 5 1/2" FROM 2456-2676'. PUMPED DOWN 4 1/2" CASING 500# HULLS 200 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN AT 200#. PUMPED DOWN 10 3/4" X 7" ANNULUS 50 SX CMT. CMT AT SURFACE. HAD HOLE IN SURFACE PIPE. ANNULUS STAYED LOADED. PUMPED DOWN 7" X 4 1/2" ANNULUS. CMT AT SURFACE. PRESSURED UP TO 500#.

RECEIVED
OCT 17 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

INVOICED

OCT 16 2002

Form SP-2/3

DATE 10-18-02

INV. NO. 2003060666 MP