

To: 1090557
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,262 -00-00

S/2 SW 33, SEC. 33, T 18 S, R 24 WAB

330 feet from S section line

1980 feet from E section line

Lease Name Harkness Well # 2

County Ness

Well Total Depth 4440 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

TECHNICIAN'S PLUGGING REPORT

Operator License #

Operator: Kansas Corporation Commission

Name:

Address 130 S. Market, Rm. 2078

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 9:40 a.m. Day: 15 Month: 6 Year: 1995

Plugging proposal received from Steve Durrant

(company name) KCC (phone) 316-225-6760

well: 4 1/2" at 4439' w/175 sx cement, PBTD 4439', Perfs at 4102-4284', DV @ 1630' w/275' sx cement

1st plug pump 2 sx hulls and 20 sx cement to bottom,

2nd plug perforate casing at 1100' and squeeze 4 1/2" casing with 200 sx cement,

3rd plug pump annulus with 180 sx cement. Attempt to circulate cement from 1100'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 15 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT Cement at 1300'-could not get through.

1st plug ran tubing to 1300' and pumped in 80 sx cement,

2nd plug pulled to 750' and pumped in 25 sx cement,

3rd plug pulled out of hole with tubing and topped off with 10 sx cement.

Backside full of cement.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed [Signature]
(TECHNICIAN)